

2-040818

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

9-16

API NUMBER: 15-095-20,202-0000  
SW, SW, SE, SECTION 34 TOWNSHIP 29 RANGE 08W

OPERATOR LICENSE # 5003 330 FEET FROM S SECTION LINE  
2310 FEET FROM E SECTION LINE

OPERATOR McCOY PETRO. CORP.  
NAME & 3017 CURPRESS  
ADDRESS WICHITA, KS 67226

LEASE NAME: RICHARDSON #2  
COUNTY: KM  
WELL TOTAL DEPTH: 4270 PB 4236'

138.78'

PIPE: \_\_\_\_\_

SURFACE CASING: 8 5/8" @ 254'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL X INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE  
ADDRESS: ATTICA, KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: JANE GREEN  
COMPANY NAME: McCOY PETRO. CORP. PHONE: \_\_\_\_\_  
WERE: 4 1/2" @ 4268', SAND TO 4100' & 4 XS. PERF. @ 4150-4190' PBTD 4236; 35 XS. @ 1200', 35 XS. @ 805', CIRC. CMT. @ 300'. CASING LK. 650-670'.

PLUGGING PROPOSAL RECEIVED BY: \_\_\_\_\_

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART ( X ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 12:00 DAY: 16 MONTH: 9 YEAR: 1995

ACTUAL PLUGGING REPORT:

DUMP SAND TO COVER PERFS FROM 4236'-4100'. FOUND COLLAPSED CASING @ 3500'. SPOTTED 35 XS. CMT. @ 3500' RECOVERED CASING FROM 1200' & PULLED FROM WELLBORE. RAN 2 3/8" TUBING TO 1200' SPOTTED 35 XS. CMT. PULLED UP TO 805' SPOTTED 35 XS. CMT. PULLED CASING TO 309' & CIRC. CMT. TO SURFACE PULLED TUBING AND TOPPED OF CMT.

REMARKS: ALLIED CMT. 60/40 4% GEL.

I DID OBSERVE THIS PLUGGING.

  
Steve Van Gieson (AGENT)

RECEIVED  
FORM CP-2/3  
REV. 3/90  
KANSAS CORPORATION COMMISSION

INVOICED

DATE 10-31-95

INV. NO. 43904

OCT 26 1995

CONSERVATION DIVISION  
WICHITA, KS

AW