

2100084

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 095-21,549-0000 *P*

SE NW NE, SEC. 30, T 29 S, R 8 *WEX*  
4290 feet from N/S section line  
1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5041

Lease Name Rickard Well # 1

Operator: Ram Petroleum Corporation  
Name & Address: 1260 KSB Building  
Wichita, KS 67202

County Kingman 138.19

Well Total Depth 4252 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet *307'*  
*250 307'*

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30 Inc. License Number 5107

Address Wichita, KS

Company to plug at: Hour: a.m. Day: 27 Month: 11 Year: 19 85

Plugging proposal received from \_\_\_\_\_

(company name) H-30 (phone) \_\_\_\_\_

were: 35 sacks at 1000 feet ; 35 sacks at 300 feet ; 15 sacks at 40 feet and  
bridge ; 10 sacks in rat hole ; 10 sacks in mouse hole

Plugging Proposal Received by \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 5:30 Day: 27 Month: 11 Year: 19 85

ACTUAL PLUGGING REPORT Filled hole with mud to 1100 feet and spotted 35 sacks of cement.  
Filled with mud to 300 feet and spotted 35 sacks of cement. Pulled pipe, set wood and  
rubber plug at 40 feet and spotted 15 sacks of cement. Ran one joint of pipe in rat hole  
and circulated 10 sacks of cement to surface. Circulated 10 sacks in mouse hole.

Remarks: Allied #2061  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DEC 18 1985

RECEIVED  
STATE CORPORATION COMMISSION

DEC 16 1985

Signed *J.L. San Juan*  
(TECHNICIAN)

DATE \_\_\_\_\_  
INV. NO. 11607

CONSERVATION DIVISION  
Wichita, Kansas

Starting Date: November 18, 1985  
month day year

API Number 15- 095-21,549-0000

OPERATOR: License # 5041  
Name Ram Petroleum Corporation  
Address 1260 KSB Bldg.  
City/State/Zip Wichita, Kansas 67202  
Contact Person Jon M. Callen  
Phone 265-5241

SE NW NE Sec. 30 Twp. 29 S, Rg. 8  
4290' East  
1650' West  
Ft. from South Line of Section  
Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5107  
Name H-30, Inc.  
City/State 251 N. Water #10, Wichita, Ks.

Nearest lease or unit boundary line 990 feet  
County Kingman  
Lease Name Rickard Well # 1

Well Drilled For: Well Class: Type Equipment:  
 Oil  SWD  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Ground surface elevation feet MSL  
Domestic well within 330 feet: \_\_\_yes \_\_\_no  
Municipal well within one mile: \_\_\_yes  no  
Surface pipe by Alternate: 1  2 \_\_\_  
Depth to bottom of fresh water 200' ~ 100'  
Depth to bottom of usable water 200'  
Surface pipe planned to be set 250'  
Projected Total Depth 4250' feet  
Formation Mississippi

If OWWO: old well info as follows:

Operator  
Well Name  
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

\_\_\_\_\_ cementing will be done immediately upon setting production string.  
Date 11-11-85 Signature of Operator or Agent Jon M. Callen Title Vice-Pres. Operations

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required feet per AP 1 2

This Authorization Expires 5-3-86 Approved By 11-13-85