

2 100566

2-26

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-21,632-0000

SW SE, SEC. 4, T. 29 S, R. 10W (W/E)

660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Eck Well # 1

Operator: National Coop Refinery Assoc

County Kingman 93.27

Name & Address 1775 Sherman St., #3000

Well Total Depth 2870 feet

Denver, CO 80203

Conductor Pipe: Size feet

303-861-4883

Surface Casing: Size 8-5/8 feet 305'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling License Number 5420

Address El Dorado, KS 1416 West 6th St.

Company to plug at: Hour: 7:00a Day: 26 Month: 2 Year: 1990

Plugging proposal received from Floss

(company name) White & Ellis (phone)

were: 1550' - 35 sx

1000' - 35 sx

360' - 35 sx

60' - 25 sx

R.H. - 10 sx

Plugging Proposal Received by Jack Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:00a Day: 26 Month: 2 Year: 19 90

ACTUAL PLUGGING REPORT Spot 35 sx at 1550' below salt - pull pipe to 1000' - spot

35 sx cmt above salt - pull pipe to 360' - spot 35 sx cmt below surface pipe -

pulled pipe to 60' & spotted 25 sx to surface - put 10 sx in rat hole

RECEIVED STATE CORPORATION COMMISSION

MAR 7 4 1990

CONSERVATION DIVISION
Wichita, Kansas

Remarks: B.J. Titan #551690 60/40 4%

(If additional description is necessary, use BACK of this form.)

XXXXXX did not observe this plugging.

DATE 3-16-90

Signed J.L. Sanders (TECHNICIAN)

NV. NO. 27695

m