

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21801-00-00
Spot: CNWSW Sec/Twnshp/Rgc: 4-29S-10W
1980 feet from S Section Line, 660 feet from W Section Line
Lease/Unit Name: FREUND Well Number: 1
County: KINGMAN Total Vertical Depth: 2660 feet

Operator License No.: 5430
Op Name: ENERGY THREE, INC.
Address: 1430 LELIA DRIVE STE 200
JACKSON, MS 39216

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 208 **886.45**
Production: Size _____ feet:
Liner: Size _____ feet:

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/21/2001 10:00 AM

Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.

Proposal Rcvd. from: MIKE PICKRELL Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: 35 sxs. cement at 850', 35 sxs. cement at 250', 25 sxs. cement at 60, 15 sxs. cement in rat hole, and 10 sxs. cement in mouse hole.

Plugging Proposal Received By: JACK LUTHI

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 10/21/2001 11:15 AM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Filled hole with heavy mud and spotted plugs through drill pipe. Spotted 35 sxs. cement at 800', spotted 35 sxs. cement at 250', spotted 25 sxs. cement at 60' filled rat hole with 15 sxs. cement, and filled mouse hole with 10 sxs. cement.

RECEIVED
KCC DISTRICT #2

NOV 02 2001

WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED. INVOICE #8590.

Plugged through: DP

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED

DATE 11-05-01

INV. NO. 2002060913