

6-5

2-040890

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-095-21,729-0000

NW SE NE, SECTION 15 TOWNSHIP 29 RANGE 7W

OPERATOR LICENSE # 31632 3630 FEET FROM S SECTION LINE

OPERATOR BISON PRODUCTION COMPANY 990 FEET FROM E SECTION LINE

NAME & 9320 EAST CENTRAL

ADDRESS WICHITA, KS 67206

LEASE NAME: HARRISON #1-15

COUNTY: KINGMAN

WELL TOTAL DEPTH: 4210' 136.83

PIPE: _____

SURFACE CASING: 8 5/8" @ 210'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: DUKE DRILLING COMPANY

ADDRESS: _____ LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: JOHN ARMBRUSTER

COMPANY NAME: DUKE DRILLING COMPANY PHONE: _____

WERE: 35 SACKS AT 1100'

35 SACKS AT 700'

100 SACKS AT 260'

15 SACKS IN RATHOLE, 10 SACKS IN MOUSEHOLE

PLUGGING PROPOSAL RECEIVED BY: DISTRICT II

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE (X)

COMPLETED: HOUR: 3:30 DAY: 5 MONTH: 6 YEAR: 1997

ACTUAL PLUGGING REPORT: THE DRILLING PIPE WAS RUN TO 1100' WHERE 35 SACKS OF CEMENT WAS SPOTTED. THE DRILL PIPE WAS PULLED TO 700' WHERE 35 SACKS OF CEMENT WAS SPOTTED. THE DRILL WAS PULLED TO 260' WHERE CEMENT WAS CIRCULATED TO SURFACE. 15 SACKS OF CEMENT WAS CIRCULATED IN THE RATHOLE AND 10 SACKS OF CEMENT WAS SPOTTED IN THE MOUSEHOLE.

RECEIVED
KANSAS CORPORATION COMMISSION

REMARKS: 60/40 POZ ALLIED CEMENT SEP 11 1997

CONSERVATION DIVISION
WICHITA, KS
I DID NOT OBSERVE THIS PLUGGING.
[Signature]
STEVE VAN GIESON

INVOICED
DATE 9-11-97
INV. NO. 48960