

7-13

2 070168

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- completion date 12/4/52

SE, SEC. 16, T 29 S, R 7 W&E

2310 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Brand "B" Well # 1

Operator: Oxy USA Inc.

County Kingman 151.74

Name & Address P. O. Box 26100

Well Total Depth 4669 feet

Oklahoma City, OK 73126

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8-5/8 feet 191

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Hays Well Service License Number \_\_\_\_\_

Address Attica, KS

Company to plug at: Hour: 9:00 Day: 13 Month: 7 Year: 19 89

Plugging proposal received from Don Herman

(company name) Oxy (phone) 405-749-2000

were: Sand to 3500' & 5 sx - 35 sx at 1300' - 35 sx at 800' - 250' to surface

Plugging Proposal Received by W.K.  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 11:00 Day: 13 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT Sanded bottom to 3500' & 5 sx common - pulled 3046' of 5-1/2"  
& ran 2-3/8 tubing to 1300' & pumped 35 sx of 65/35 4% - pulled tubing to 800' &  
pumped 35 sx - pulled to 250' & pumped 100 sx to surface - 75 sx 65/35 4% and  
25 sx were common - pumped by Halliburton

RECEIVED  
STATE CORPORATION COMMISSION

JUL 24 1989

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: \_\_\_\_\_

INVOICED

(If additional description is necessary, use BACK of this form.)

(did / ~~not~~ observe this plugging.)

DATE 7-25-89

Signed [Signature]  
(TECHNICIAN)

INV. NO. 25402