

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21754-00-~~PO~~OL
Spot: W2NWSE Sec/Twnshp/Rge: 20-29S-7W
1980 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: MAYER Well Number: 1
County: KINGMAN Total Vertical Depth: 4541 feet

Operator License No.: 6236
Op Name: M.T.M. PETROLEUM
Address: PO BOX 82
SPIVEY, KS 67142

Conductor Pipe: Size _____ feet: 8 1/47.58
Surface Casing: Size 8.625 feet: 256 175 SX CMT
Production: Size 5.5 feet: 4509 100 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/11/2002 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE Phone: (316) 727-3410

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 07/11/2002 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perms were covered w/sand from 4541'- 4130', and capped w/5sxs of cement. The pipe was shot at 3900', 3500', 2400' and came loose at 2000'. The pipe was pulled to 1170' where 35sxs of cement was spotted. The pipe was pulled to 700', where 35sxs of cement was spotted. The pipe was pulled to 300' where cement was circulated to surface.

RECEIVED
KCC DISTRICT #2

JUL 15 2002

WICHITA, KS

Remarks: UNITED CEMENT 60/40 POZ. 4% GEL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED

DATE 7-22-02

INV. NO. 2003060077