

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21816-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 20-29S-7W
990 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: MAYER Well Number: 2
County: KINGMAN Total Vertical Depth: 4543 feet

Operator License No.: 6236
Op Name: M.T.M. PETROLEUM
Address: PO BOX 82
SPIVEY, KS 67142

Production Casing Size: 4.5 feet: 4234 125 SX CMT
Surface Casing Size: 8.625 feet: 233 165 SX CMT

149 65

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/09/2003 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: AS KCC REQUIRES

RECEIVED
KCC DISTRICT #2
OCT 2 2003

WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON
Date/Time Plugging Completed: 07/11/2003 10:00 AM

Witness Type: Plugging Operations Partially Witnessed
KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4062', AND CAPPED WITH 4 SKS OF CEMENT. THE CASING WAS RECOVERED FROM 3617', AND PULLED TO 1200', WHERE 35 SKS OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 700', WHERE 35 SKS OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 300' WHERE CEMENT WAS CIRCULATED TO SURFACE.

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 06 2003

CONSERVATION DIVISION
RECEIVED
KANSAS CORPORATION COMMISSION

OCT 06 2003


CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

INVOICED

10-16-03
2004060582