

2-23

15-095.00522-0000 98  
2-040760 R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 10-25-56

SW NE NW, SECTION 22 TOWNSHIP 29 RANGE 7W

OPERATOR LICENSE # 5447 4290 FEET FROM S SECTION LINE  
3630 FEET FROM E SECTION LINE

OPERATOR OXY USA, INC.  
NAME & 100 S. MAIN, #800  
ADDRESS WICHITA, KS 67202

RECEIVED  
KANSAS CORPORATION COMMISSION

LEASE NAME: VORAN B-1  
COUNTY: KINGMAN

MAR 09 1993

WELL TOTAL DEPTH: 4506' 146.44

CONSERVATION DIVISION  
WICHITA, KS

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 400'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL X INPUT WELL \_\_\_\_\_ SLD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: \_\_\_\_\_  
ADDRESS: \_\_\_\_\_ LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: \_\_\_\_\_

COMPANY NAME: \_\_\_\_\_ PHONE: \_\_\_\_\_

WERE: 5-1/2" @ 4192' - PERFS 4126-31' - SAND TO 4050' & 4 SX  
- 45 SX 1200' - 45 SX 800' - CIR CMT 450' TO 0'

PLUGGING PROPOSAL RECEIVED BY: \_\_\_\_\_

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART ( X ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 1615 DAY: 23 MONTH: 2 YEAR: 1993

ACTUAL PLUGGING REPORT:  
PERFS COVERED W/SAND TO 4050' & CAPPED W/4 SX CMT -  
5-1/2" PERFED @ 1200' - PKR ON TUB RUN 1173' & 45 SX  
CMT SPOTTED & DISPLACED OUT OF TUB THRU THE PERFS  
LEAVING 2 BBLs SLURRY IN 5-1/2" - PERFS SHOT @ 800' &  
45 SX CMT DISPLACED TO 750' - PERFS SHOT AT 450' & CMT  
CIRC TO SURFACE.

REMARKS: ALLIED #2937 90 SX COM 2% CAL - 250 SX 60/40 4% GEL

INVOICED  
I DID OBSERVE THIS PLUGGING.

DATE 3-16-93

BY 37426

HS  
Steve Van Gieson (AGENT)

FORM CP-2/3  
REV. 3/90

APR 06 1993 MAY 12 1993

DW