

To: 1 100083
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-175-20,778-0000

NW NW NE, SEC. 33, T 32 S, R 34 W/E

4950 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5447

Lease Name Hitch P Well # 1

Operator: OXY USA Inc.

County Seward 209.62

Name & Address P.O. Box 300

Well Total Depth 6450 feet

Tulsa, OK 74102-0300

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1699

Abandoned Oil Well Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 22 Month: 11 Year: 19 96

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 6441' w/325 sx cement, PBD 6401', Perfs at 6152-58'

1st plug set CIBP at 6100' with 2 sx cement on top,

2nd plug at 3100' with 80 sx cement,

3rd plug at 1700' with 50 sx cement,

4th plug at 700' with 50 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:30 p.m. Day: 22 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug spotted 25 sx Halliburton lite at 6168-5900',

2nd plug shot at 3100' and pumped 80 sx cement, displaced to 2700',

3rd plug shot at 1742' and pumped 50 sx cement,

4th plug pulled to 700' and pumped 35 sx cement,

5th plug pumped 10 sx cement from 40-0'.

Remarks: Used common cement by Sargent's. Recovered 1742' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

I (did) observe this plugging.

Signed Gary Winters (TECHNICIAN)

INVOICED
DATE DEC 03 1996

INV. NO. 47086

11-22 JAN 28 1997

RECEIVED
1996 NOV 27 A 2:07