

11-22

1 080008

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-20,989-0000
SW NW, SEC. 1, T 32 S, R 42 W/EX
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5263
Operator: Midwestern Exploration Company
Name & Address P.O. Box 1884
Liberal, KS 67905-1884.

Lease Name Baughman Well # 1-1
County Morton 169.16
Well Total Depth 5205 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1501

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Jerry Dunkin, Inc. License Number 8733
Address P.O. Box 389, Enid, OK 73702

Company to plug at: Hour: 12 p.m. Day: 22 Month: 11 Year: 1989

Plugging proposal received from Butch Dunkin

(company name) Jerry Dunkin, Inc. (phone) 405-237-6152

were: 4 1/2" at 5205' PBD 3140' Perfs at 3052-66, 3120-28'

1st plug pump 1 sx hulls and 25 sx cement, Spot through casing:

2nd plug pump 50 sx cement at 1530', 3rd plug pump 40 sx cement at 750',

4th plug pump 10 sx cement at 40-0'

Plugging Proposal Received by Mike Spain
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:15 p.m. Day: 22 Month: 11 Year: 1989

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement, Spotted through casing:

2nd plug pumped 50 sx cement at 1530',

3rd plug pumped 40 sx cement at 750',

4th plug pumped 10 sx cement at 40-0'.

RECEIVED
STATE CORPORATION COMMISSION

NOV 28 1989

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used Class H cement by Jerry Dunkin, Inc. Recovered 2436' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-6-89

INV. NO. 26645

Signed Mike Spain
(TECHNICIAN)