

1100313

TO: STATE CORPORATION COMMISSION

API NUMBER 15-129-21,590-0000
C NE/4 SEC. 5, T 32, S, R 42 W

CONSERVATION DIVISION - PLUGGING SECTION 3890 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1250 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HANKE TRUST WELL # 1-5

TECHNICIAN'S PLUGGING REPORT

COUNTY MORTON 109.17

OPERATOR LICENSE # 8061

WELL TOTAL DEPTH 3359' FEET

OPERATOR: OIL PRODUCERS INC. OF KANSAS PRODUCTION CSG: SIZE 4 1/2" @ 3358' WITH 410 SX

NAME AND PO BOX 8647 SURFACE CASING: SIZE 8 5/8" @ 515' WITH 250 SX

ADDRESS WICHITA, KS 78208-8674

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR ALLIED CEMENTING COMPANY, INC LICENSE NUMBER NA

ADDRESS PO BOX 31 RUSSELL, KS 67665-0031

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 03 MONTH: 11 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MAX BALL

(COMPANY NAME) ALLIED CEMENTING COMPANY (PHONE) 785-483-2627

WERE: PERFS AT 2755-3295 NOTE: IT TOOK 30 MINUTES TO GET THE WELL TO BLOW DOWN THROUGH 2" VALVE ON TOP. WELL CONTINUED TO VENT SLIGHTLY WHILE HOOKING UP. NOT SURE IF ANY COMPLETION WORK WAS DONE ON THIS WELL.

1ST PLUG MIX 300# HULLS FOLLOWED BY 175 SX CEMENT AND FILLED 4 1/2" CASING TO SURFACE WITH CEMENT. MAXIMUM PRESSURE AT 500# AFTER 175 SX CEMENT WAS MIXED. 2ND PLUG CONNECTED UP ON 8 5/8" X 4 1/2" ANNULUS. AFTER 10 SX CEMENT WAS MIXED SAW PRESSURE OF 700#.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE

OPERATIONS COMPLETED: HOUR: 11:00 AM DAY: 03 MONTH: 11 YEAR: 1999

ACTUAL PLUGGING REPORT _____

1ST PLUG MIX 300# HULLS FOLLOWED BY 175 SX CEMENT AND FILLED 4 1/2" CASING TO SURFACE WITH CEMENT. ACHIEVED PRESSURE OF 500 PSI AFTER 175 SX CEMENT WAS MIXED. 2ND PLUG CONNECTED UP ON 8 5/8" X 4 1/2" ANNULUS. AFTER 10 SX CEMENT WAS MIXED SAW PRESSURE OF 700#.

RECEIVED
STATE CORPORATION COMMISSION
11-10-99
NOV 10 1999

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

DATE: 12/7/99
(OBSERVE THIS PLUGGING.)

CONSERVATION DIVISION
Wichita, Kansas

SIGNED Gary Winters
(TECHNICIAN) FORM CP-2/3

INV. NO. 60931