

1031047

11-29

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 189-20,867-0000
C NE SW, SEC. 12, T 32 S, R 35 W/E
1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5398
Operator: ARCO Oil & Gas Company
Name & Address P.O. Box 1610
Midland, TX 79702

Lease Name Holt "A" Well # 1
County Stevens 209.63
Well Total Depth 6450 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1714

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Dowell Schlumberger, Inc. License Number _____
Address P.O. Box 887, Ulysses, KS 67880

Company to plug at: Hour: 10:30 a.m. Day: 29 Month: 11 Year: 1989

Plugging proposal received from Doug Holt

(company name) ARCO Oil & Gas Company (phone) 316-356-1272

were: 5 1/2" at 6414' PBD 4505' Perfs at 4281-4521'

1st plug set CIBP at 4225' with 4 sx cement on top,

2nd plug pump 20 sx cement at 1756',

3rd plug pump 200 sx cement from 750-0'.

Plugging Proposal Received by Steve Dumont
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 29 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4200' with 4 sx cement on top,

2nd plug pumped 20 sx cement at 1756',

3rd plug pumped 206 sx cement at 750-0'.

Witnessed by Ed Knobloch

Remarks: Used Class H Cement by Dowell. No casing recovery.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
DEC 5 1989

INVOICED

DATE 12-7-89

INV. NO. 36701

Signed Steve Dumont
(TECHNICIAN)