

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20781-00-00
Spot: CS2NW Sec/Twnshp/Rge: 12-32S-35W
3300 feet from S Section Line, 3960 feet from E Section Line
Lease/Unit Name: NIPPLE Well Number: 1
County: STEVENS Total Vertical Depth: 6450 feet

Operator License No.: 31269
Op Name: BELCO ENERGY CORP.
Address: 5735 PINELAND STE 300
DALLAS, TX 75231

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 1797 WITH 900 SX CMT
Production: Size 5.5 feet: 6450 WITH 1400 SX CMT
Liner: Size _____ feet: _____ 209.63

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/21/2001 11:30 AM
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.
Proposal Rcvd. from: BUTCH DUNKIN Company: DUNKIN, JERRY, INC. Phone: (580) 237-6152

Proposed Plugging Method: CIBP @ 5480' WITH 2 SX CMT. 1ST PLUG AT 1820' WITH 40 SX CMT THROUGH TUBING. 2ND PLUG AT 550' WITH 40 SX CMT THROUGH CASING. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/21/2001 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6406'. DV TOOL @ 3613' WITH 600 SX CMT. TOC 600'. PERFS AT 5991-6012, 5520-5527'. SET CIBP @ 5290' WITH 2 SX CMT ON TOP. FILL HOLE WITH MUD. 1ST PLUG RUN IN HOLE WITH TUBING TO 1820' & PUMP 40 SX CMT. 2ND PLUG PULL TUBING TO 580' AND PUMP 40 SX CMT. 3RD PLUG PULL TUBING TO 60' AND PUMP 20 SX CMT.

INVOICED
DATE 6-25-01
INV. NO. 2001061976

RECEIVED
KANSAS CORPORATION COMMISSION
6-25-01
JUN 25 2001

CONSERVATION DIVISION


Remarks: USED COMMON CEMENT BY ALLIED. RECOVERED 600' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

Signed Jim Holland PART II
(TECHNICIAN)

JUN 22 2001


Form CP-2/3

