

To: 100170 10-24
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 189-20,694-0002
NE NW NE, SEC. 26, T 32 S, R 35 W/E
151 feet from NSX section line
1926 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Lease Name Boles #1 Unit Well # 3

Operator: Mobil Oil Corporation

County Stevens 207.35

Name & Address P.O. Box 2173

Well Total Depth 6380 feet

Liberal, KS 67905-2173

Conductor Pipe: Size _____ feet

Surface Casing: Size 9 5/8 feet 1760

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Dowell/Schlumberger License Number _____

Address _____

Company to plug at: Hour: 9 a.m. Day: 24 Month: 10 Year: 1997

Plugging proposal received from Tom Romaro 10-28-97

(company name) Mobil Oil Corporation (phone) 316-544-5547

were: 5 1/2" at 6380' w/735 sx cement. CIBPs at 2910, 6190', Perfs at 6240-64'

1st plug CIBPs set at 6190' and 2910' with 2 sx cement on top,

2nd plug perforate at 1760' and circulate cement in and out of 9 5/8".

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 24 Month: 10 Year: 1997

ACTUAL PLUGGING REPORT 1st plug set CIBPs at 6190' and 2910' with 2 sx cement on top,

2nd plug perforate at 1790' with 4 shots. Pumped 520 sx cement, circulated cement to surface inside 5 1/2" and 9 5/8". X 5 1/2" annulus.

Remarks: Used 60/40 Pozmix 6% gel by Dowell/Schlumberger. No casing recovery.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE OCT 29 1997

Signed Gary Winter
(TECHNICIAN)

INV. NO. 49375