

1 060461

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,790-0000
C SW NE, SEC. 17, T 32 S, R 32 W/E

3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5253

Lease Name Alexander Well # NK 3-17

Operator: Northern Pump Company

County Seward 145.60

Name & Address Box 937

Well Total Depth 4480 feet

Garden City, KS 67846

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1656

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor J. B. Bohannan License Number 5879

Address Box 6, Liberal, KS 67901

Company to plug at: Hour: 6:30 pm Day: 4 Month: January Year: 19 85

Plugging proposal received from J. B. Bohannan

(company name) J. B. Bohannan (phone) 316-624-2202

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2900' with 50 sx cement

2nd plug at 1700' with 50 sx cement

3rd plug at 850' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Paul A. Tuttle
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:20 pm Day: 4 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2900' with 50 sx cement, 2nd plug at 1700' with

50 sx cement, 3rd plug at 850' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Dowell

JAN 15 1985

(If additional description is necessary, use BACK of this form.)

INVOICED

(check or not) observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Tuttle
(TECHNICIAN)

DATE 1-22-85

INV. NO. 6611 1-4

FEB 18 1985

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: Nov 1 1984
month day year

API Number 15- 175-20,790-0000

OPERATOR: License # 5253
Name Northern Pump Company
Address Box 937
City/State/Zip Garden City, Kansas 67846
Contact Person J. Leo Fife
Phone 316-276-3267

C SW/4 NE/4 Sec 17 Twp 32 S, Rge 32 East
(location) West
3,300 Ft North from Southeast Corner of Section
1,980 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5879
Name J. B. Bohannon 316-624-
City/State Liberal, Kansas 67901 2202

Nearest lease or unit boundary line 1,980 feet.
County Seward
Lease Name Alexander Well # NK3-17
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWW Expl Wildcat Cable

Depth to Bottom of fresh water 550 feet
Lowest usable water formation 550
Depth to Bottom of usable water 600 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 1,600 feet
Conductor pipe if any required 40 feet
Ground surface elevation Approx 2,800 feet MSL
This Authorization Expires 4-5-85
Approved By 10-5-84

If OWWC: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4,600 feet
Projected Formation at TD Lansing
Expected Producing Formations Lansing
Certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

to 10-4-84 Signature of Operator or Agent J. Leo Fife Title Prod. Supt.

T-W Water
Liberal well
350'
deep
nm HC / NONE 10/5/84
Form C-1 4/84

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1985
CONSERVATION DIVISION
Wichita, Kansas