

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20003-00-00
Spot: SWNW Sec/Twnshp/Rge: 26-32S-41W
1980 feet from N Section Line, 660 feet from W Section Line
Lease/Unit Name: GOING A Well Number: 3
County: MORTON Total Vertical Depth: 5010 feet

Operator License No.: 4549 Production Casing Size: 4.5 feet: 3272 WITH 210 SX CMT
Op Name: ANADARKO PETROLEUM CORPORATI Surface Casing Size: 8.625 feet: 1486 CIRCULATE
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

Well Type: GAS UIC Docket No: Date/Time to Plug: 09/04/2003 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 3090'. PLUG AT 1490' WITH 50 SX CMT. PLUG AT 700' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/04/2003 2:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:
PBTD 3230'. PERFS AT 3138-3146'. SET CIBP @ 3090' WITH 2 SX CMT. LOAD HOLE WITH MUD & PRESSURE TO 500#. 1ST PLUG PULL OUT OF HOLE TO 1490'. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 700'. LOAD HOLE & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED
OCT 01 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1538' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
SEP 15 2003
KCC Dodge City

Signed

Jim Holland
(TECHNICIAN)

INVOICED
DATE 10-1-03
INV. NO. 2004060558

Form CR 2/B