

2040116

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-09521470-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Operator Name: Energy Three, Inc  
Address: P.O. Box 1505  
Great Bend Ks. 67530

SEC. 24, T 30 S, R 16 W/E

4950 feet from N/S section line

1650 feet from W/E section line

Lease Name Cotton Well # 1

County Kingman

Well Total Depth 4580 148.85 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Brandt Drilg. Co. License Number 5840

Address Wichita Ks. 67202

Company to plug at: Hour: 2030 Day: 12 Month: 9 Year: 19 84

Plugging proposal received from Jim Moore

(company name) Brandt Drilg. Co. (phone) \_\_\_\_\_

were: 35 SX 1050

35 SX 270

25 SX 60

10 SX RH

Plugging Proposal Received by Glen Ward (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2315 Day: 12 Month: 9 Year: 19 84

ACTUAL PLUGGING REPORT

Filled hole with heavy mud, ran drill pipe to 1050, spotted 35 sb of cement. Pulled pipe to 270' and spotted 35 sb of cement. Pulled pipe from hole, dumped 1 sb hulls and pushed Wood B Rubber plug to 50' and filled hole with cement. Circulated 10 sb of cement in rat hole

Remarks: 60/40 Poz-MN 3% cc 2% gel

STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.)

SEP 25 1984

INVOICED

DATE 9-27-84

INV. NO. 3884

(If additional description is necessary, use BACK of this form.)

Signed [Signature] (TECHNICIAN)

CONSERVATION DIVISION Wichita, Kansas