

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21274-00-01 Spot: E2W2NE
Sec: 34 Twnshp & Dir: 34 S Rng & Dir: 3 W
Feet: 1320 frm N/S: N Feet: 1650 frm E/W: E
Lease/Unit Name: CATHERINE Well Number: 1
County: SUMNER Total Vertical Depth: 4890 feet

Operator License No.: 4941
Operator Name: Union Valley Petroleum Corpor
Address: RR 4, Box 120 Y
Enid, OK 73701

8/17

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 281
Production: Size 5.5 feet: 4890

158.93

Well Type: GAS UIC Docket No: Date/Time to Plug: 06/16/2000 12:00 AM
Plug Co. License No.: 8733 Plug Co. Name: Dunkin, Jerry, Inc.
Proposal Received from: Paul Youngblood Company Name: Union Valley Petro. Corp.
OpRepPhoneNo: (580) 237-3979

Proposed Plugging Method: Perfs. 4502'-4604'. Set CIBP 50' above the perfs. Shoot casing and pull to 700', and spot 35sxs of cement. Pull casing to 330' and circulate cement to surface. Pull pipe and top off cement.

Plugging Proposal Received By: Steve Van Gieson Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 08/17/2000 12:00 PM

Actual Plugging Report:

A CIBP was set at 4184'. The casing was shot loose at 2980' and pulled to 700', where 35sxs of cement was spotted. The casing was pulled to 330', where cement was circulated to surface. The remaining pipe was pulled from the wellbore and the cement was topped off. Plate welded on top of surface pipe.

RECEIVED
KCC DISTRICT #2
AUG 31 2000
WICHITA, KS

Remarks: Jerry Duncan performed cementing services. Class A cement
Anhydrite Plug: No Bottom Plug: Dakota Plug: No
Plugged through:

I (did / did not) observe this plugging.

INVOICED

Signed

(TECHNICIAN)

DATE 9/8/00
WEL. NO. 2001060617