

TG: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20615-00-00
Spot: NESE Sec/Twnshp/Rge: 13-33S-43W
1980 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: HARMON B Well Number: 4
County: MORTON Total Vertical Depth: 4784 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ ST
HOUSTON, TX 77227

Conductor Pipe Size: 21 feet: 44 WITH 4.5 YDS CMT
Production Casing Size: 5.5 feet: 4784 WITH 225 SX CMT
Surface Casing Size: 8.625 feet: 1375 WITH 600 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/11/2003 2:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PLUG AT 1400' WITH 50 SX CMT. PLUG AT 350 WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/12/2003 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 4610'. PERFS AT 4581-85, CMT RET. @ 4610'. PERFS AT 4614-18'. FL @ 700'. RUN IN HOLE WITH WIRELINE & STACKED OUT @ 4466'. FILL INSIDE OF 5 1/2" 100'+ ABOVE PERFS. SET CIBP @ 4370' WITH 2 SX CMT. 1ST PLUG PULL OUT OF HOLE TO 1400'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH 5 1/2" TO 350'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED
JUN 23 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2023' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PIRTA
(TECHNICIAN)

INVOICED

DATE: 6.24.03
AMOUNT: 200.3061675

Form 28-23