

2 100329

6-16-88

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-20,415 - 0000

C NE NW, SEC. 27, T 29 S, R 8 W/X

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5153

Lease Name Cord Well # 2

Operator: Texaco, Inc.

County Kingman 139.07

Name & Address

Well Total Depth 4279 PBD 4232 feet

Box 2420

Conductor Pipe: Size 5 1/2" feet 4199

Tulsa, OK 74102

Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67905

Company to plug at: Hour: 3:00pm Day: 1 Month: 6 Year: 1988

Plugging proposal received from Elmo

(company name) Clarke Corporation (phone) _____

were: Sand to 4100' and dump 5 sxs cement w/bailer. Shoot and pull 5 1/2". Pump

3 hulls, 12 sxs gel and 125 sxs 60/40 poz, 2-4% gel.

Plugging Proposal Received by J. L. Sanders
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00pm Day: 16 Month: 6 Year: 1988

ACTUAL PLUGGING REPORT Sanded bottom to 4110' and dumped 5 sxs cement. Shot and pulled

2749' of 5 1/2". Pumped through swedge 3 sxs hulls, 12 sxs gel and 100 sxs

cement with 2 1/2" pipe then 250 sxs on top.

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1988
CONSERVATION DIVISION
Wichita, Kansas

Remarks: B.J. Titan #422139 600# oper 600# Shutin
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby agree to observe this plugging.

DATE 6-30-88

Signed J. L. Sanders ps
(TECHNICIAN)

INV. NO. 21147

Wk