

2 100.330

6-16-88

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- ⁰⁹⁵ ~~0975~~-20,016 - 0000

C NW NE, SEC. 27, T 29 S, R 8 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5153

_____ feet from S section line

_____ feet from E section line

Operator: Texaco, Inc.

Lease Name Cord Well # 1

Name & Address

County Kingman 137.12

Box 2420

Well Total Depth 4219 feet

Tulsa, OK 74102

Conductor Pipe: Size 5 1/2" feet 4199

Surface Casing: Size 8 5/8" feet 256

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Liberal, KS 67901

Company to plug at: Hour: 9:00am Day: 1 Month: 6 Year: 19 88

Plugging proposal received from Elmo

(company name) Clarke Corporation (phone) _____

were: Pump 25 sxs cement w/top at 4100'. Shoot and pull 5 1/2" to 300'. Pump 50 sxs cement @300'-200'. Pull 5 1/2" and put 10 sxs cement @40' to 0'. Cut off and cap.

Plugging Proposal Received by J. L. Sanders (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:00pm Day: 16 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT Sanded bottom to 4130' and dumped 5 sxs cement. Shot and pulled

2372' of 5 1/2" casing. Through swedge pumped 3 sxs hulls, 2 sxs gel, found

hole 10' down in surface, dog down to cement, cut 8 5/8" and welded plate,

then pumped 10 sxs gel and 125 sxs cement.

RECEIVED STATE CORPORATION COMMISSION

JUN 24 1988

Remarks: B.J. Titan #422138 CONSERVATION DIVISION 600# Shutin (If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

INVOICED

Signed J. L. Sanders (TECHNICIAN)

DATE 6-30-88 WK

INV. NO. 21146