

02-040961

8-18

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21636-00-00 Spot: S4NWSW
Sec: 36 Twnshp & Dir: 29 S Rng & Dir: 7 W
Feet: 1650 frm N/S: S Feet: 4950 frm E/W: E
Lease/Unit Name: KREHBIEL Well Number: 4
County: KINGMAN Total Vertical Depth: 4242 feet

137.87

Operator License No.: 8740
Operator Name: Bramwell Petroleum, Inc.
Address: 15183 SW 25th
Spivey, KS 67142

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 212
Production: Size 5.5 feet: 4242

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/1999 7:00 PM
Plug Co. License No.: 31529 Plug Co. Name: Mike's Testing & Salvage, Inc.
Proposal Received from: Mike Kelso Company Name: Mike's Testing & Salvage
OpRepPhoneNo: (316) 532-2770

Were: PBTD 4185', Perfs-4133-4140'. Sand to 4030' & 5 sks cement. Recover pipe, spot 35 sks cement@1100', spot 35 sks of cement @ 700'. Circulate cement from 250'-0'

Plugging Proposal Received By: Steve Van Gieson, KCC WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 08/18/1999 7:00 PM

Actual Plugging Report:

Perfs covered w/sand from 4185' to 4030', capped w/5 sks cement. Pipe recovered from 2800', pulled to 1116', 35 sks cement spotted. Pipe pulled to 702', 35 sks cement spotted. Pipe pulled to 275', cement circulated to surface. Pipe pulled/cement topped off

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 03 1999
CONSERVATION DIVISION
WICHITA, KS

Remarks: United Cementing # 1964 60/40 poz 4% gel
Anhydrite Plug: No BottomPlug: _____ DakotaPlug: No
Plugged through: _____

I (did/did not) observe this plugging.

Signed _____
(TECHNICIAN)

INVOICED
DATE 9-14-99
INV. NO. 60514