

2 040232

095-20957-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Old well
SE|NW|NW, SEC. 8, T 29 S, R 9 (W/E)

4290 feet from (S) section line

4290 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7062

Lease Name Weber Well # #1

Operator: Keener Oil Co

County Kingman

Name & Address 320 S. Boston Ste 406

Well Total Depth 4487 145.83 feet

Tulsa Oklahoma

Conductor Pipe: Size _____ feet

74103

Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Dan Kilgore

(company name) Kelso Casing Pulling (phone) _____

were: 35sx 4400, 3Hulls 15gel 110sx ^{60/40} 2% gel

4 1/2 4483.5

OH. 4483-4487

Plugging Proposal Received by St. A. Sun
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1500 Day: 17 Month: 12 Year: 19 85

ACTUAL PLUGGING REPORT On 35 sacks Plug of Cement was pushed down

the 4 1/2" casing to a depth of 4400' and shut in with 1100#.

The 4 1/2" was shot off at 3002' and recovered. The top

was squeezed plugged thru an 8 5/8" wedges by pumping

3 sacks of hulls, 15 sacks of gel and 110 sacks of 60/40

Poz-Mix Cement Ticket # 1186. SI 50# MX 350#

Remarks: Sun of Eureka just had 1 plug container and 1 sledge.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 02 1986

INV NO 11804

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1986
1-2-86
CONSERVATION DIVISION

Signed St. A. Sun
(TECHNICIAN)