

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20871-00-01
Spot: CNW Sec/Twnshp/Rge: 17-33S-43W
3960 feet from S Section Line, 3960 feet from E Section Line
Lease/Unit Name: TURNER Well Number: 2
County: MORTON Total Vertical Depth: 5150 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 5 INVERNESS DRIVE EAST STE 120
ENGLEWOOD, CO 80112

Conductor Pipe: Size feet: 167.38
Surface Casing: Size 8.625 feet: 1417 WITH 550 SX CMT
Production: Size 5.5 feet: 870 WITH 225 SX CMT
Liner: Size feet:

Well Type: SWD UIC Docket No: D25205.0 Date/Time to Plug: 09/25/2001 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & ENOUGH CMT TO FILL CASING TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/27/2001 11:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 1210'. PERFS AT 1040-70, 1130-40, 1160-70'. 5 1/2' HOLE AT 870'. 8 5/8" HOLE FROM 870-1210'. ON 09/25/01 PUMPED DOWN 5 1/2' CASING 500# HULLS - 80 SX CMT - 20 BBL MUD FOR SPACER. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 10 SX CMT & PUMP 13 BBL MUD FOR SPACER. SDON. ON 09/26/01 TAG CMT AT 880'. LOADED 5 1/2" WITH FLUID PUMPED 6 SX CMT INSIDE 5 1/2" & PUMPED 4 SX CMT DOWN BACKSIDE (FILLED TO SURFACE). NO CMT TO SURFACE INSIDE 5 1/2". FLUID AT 133'. 6 SX PLUG INSIDE 5 1/2' WENT FROM 330-400'. LET CMT SET OVERNIGHT. ON 09/27/01 FL AT 150'. PUMPED 1 BBL WATER AHEAD, PUMPED 10 SX CMT TO SURFACE IN 5 1/2".

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERY.

Plugged through: CSG

District: 01

Signed Jim Holland PIRF II
(TECHNICIAN)

RECEIVED

OCT 12 2001

KCC WICHITA

INVOICED

OCT 08 2001

DATE 10-15-01

INV. NO. 200206800

Form CP-2/3