

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20872-00-00
Spot: CNWNWNW Sec/Twnshp/Rge: 17-33S-43W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: TURNER Well Number: 3
County: MORTON Total Vertical Depth: 4860 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 5 INVERNESS DRIVE EAST STE 120
ENGLEWOOD, CO 80112

Conductor Pipe: Size feet: \$157.95
Surface Casing: Size 8.625 feet: 1418 WITH 400 SX CMT
Production: Size 4.5 feet: 4852 WITH 175 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/24/2001 11:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 4700' WITH 2 SX CMT. 1ST PLUG AT STUB WITH 40 SX CMT. 2ND PLUG AT 1740' WITH 40 SX CMT. 3RD PLUG AT 750' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/24/2001 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 4809'. PERFS AT 4712-4720'. SET CIBP @ 4700' WITH 2 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG PULL 4 1/2" TO 1440', PUMP 50 SX CMT AT BOTTOM OF SURFACE PIPE. 2ND PLUG PULL TO 750'. LOAD HOLE WITH MUD. PUMP 40 SX CMT. 3RD PLUG PULL TO 40' & PUMP 10 SX CMT.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2830' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
OCT 05 2001
KCC WICHITA

Signed

Jim Holland PART II
(TECHNICIAN)
OCT 02 2001

INVOICED

DATE 10-05-01

INV. NO. 2002060741

Form CH 2/3