

1 120379

12-12

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-20,783 - 0000

NE NE SW, SEC. 22, T 33 S, R 43 WAK

2310 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Hart A Well # 3

Operator: OXY USA Inc.
Name &
Address P.O. Box 26100
Oklahoma City, OK 73126-0100

County Morton 165.75

Well Total Depth 5100 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1352

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: Day: 8 Month: 12 Year: 19 89

Plugging proposal received from Dan Goetz

(company name) OXY USA Inc. (phone) 316-697-4427

were: 5 1/2" at 5099' PBD 4628' Perfs at 4607-4616'

1st plug set CIBP at 4570' with 2 sx cement on top,

2nd plug pump 50 sx cement at cut-off, 3rd plug pump 50 sx cement at 1400',

4th plug pump 30 sx cement at 700',

5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: Day: 12 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP from 4570-4552' with 2 sx cement,

2nd plug pumped 50 sx cement from 2800-2700',

3rd plug pumped 50 sx cement from 1400-1300',

4th plug pumped 30 sx cement from 750-650',

5th plug pumped 10 sx cement from 40-0'.

Remarks: Used common cement by Sargent's. Recovered 2814' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 3-2-90 2-28-90

Signed Duane Rankin (TECHNICIAN)

CONTRACT NO. 27595