

1 080417

API NUMBER 15- 129-20,771-0000

To: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION C SW NE, SEC. 22, T 33 S, R 43 W EX
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

3300 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Hart "A" Well # 2

Operator: Cities Service Oil & Gas Corporation County Morton 173.88

Name & Address 3545 NW 58th Street

Well Total Depth 5350 feet

Oklahoma City, OK 73112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1355

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Zenith Drilling Corporation License Number 5141

Address 505 Fourth Financial Center, Wichita, KS 67202

Company to plug at: Hour: 8:00 am Day: 8 Month: September Year: 19 85

Plugging proposal received from Glen Van Golen

(company name) Engineer for Cities Service (phone) 405-949-4342

Elevation 3611 est.

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 5350' with 35 sx cement 5th plug at 700' with 40 sx cement

2nd plug at 4488' with 50 sx cement 6th plug solid bridge - hulls -

3rd plug at 2870' with 70 sx cement 7th plug plug at 40' -- cement to surface with 10 sx cement

4th plug at 1425' with 40 sx cement 8th plug to circulate rat hole with 15 sx

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:00 am Day: 8 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 5350' with 35 sx cement, 2nd plug at 4488' with 50 sx

cement, 3rd plug at 2870' with 70 sx cement, 4th plug at 1425' with 40 sx cement, 5th plug

at 700' with 40 sx cement, 6th & 7th plugs - solid bridge - hulls - plug at 40' -- cement

to surface with 10 sx cement, 7th plug to circulate rat hole with 15 sx cement, 8th

plug to circulate mouse hole with 10 sx cement. RECEIVED

STATE CORPORATION COMMISSION

SEP 23 1985

Remarks: Used Class H cement by Halliburton CONSERVATION DIVISION

(If additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED

DATE SEP 24 1985

INV. NO. 10226

Signed J. H. Metz (TECHNICIAN)

FORM CP-2/3
Rev. 01-84

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: August 24, 1985
month day year

API Number IS- 129-20,771-0000

OPERATOR: License # 5447
Name Cities Service Oil & Gas Corporation
Address 3545 NW 58th Street
City/State/Zip Oklahoma City, OK 73112
Contact Person Raymond Hui
Phone (405) 949-4342C SW NE Sec 22 Twp 33 S, Rge 43 ☐ East
(location) ☒ West
3300 Ft North from Southeast Corner of Section
1980 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)CONTRACTOR: License # 5141
Name Zenith Drllg. Corp.
City/State Wichita, Kansas

Nearest lease or unit boundary line 1980 feet.

County Morton

Lease Name Hart "A" Well# 2

Domestic well within 330 feet: ☐ yes ☒ noMunicipal well within one mile: ☐ yes ☒ noWell Drilled For: Well Class: Type Equipment:
☒ Oil ☐ Swd ☐ Infield ☒ Mud Rotary
☐ Gas ☐ Int ☐ Pool Ext. ☐ Air Rotary
☐ OWWO ☐ Expl ☒ Wildcat ☐ Cable

Depth to Bottom of fresh water Est. 250 feet

Lowest usable water formation Ogallala

Depth to Bottom of usable water Est 350 feet

Surface pipe by Alternate: 1 ☒ 2 ☐

Surface pipe to be set Approx. 1350 feet

Conductor pipe if any required feet

Ground surface elevation Est. 3611 feet MSL

This Authorization Expires 2-21-86

Approved By RCH 8-21-85

If OWWO: old well info as follows:

Operator

Well Name

Comp Date Old Total Depth

Projected Total Depth 5500 feet

Projected Formation at TD St. Louis

Expected Producing Formations Up. Morrow, Marmaton,
St. Louis

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 8-19-85 Signature of Operator or Agent Raymond Hui Title Supervisor, Oil & Gas Systems

Form C-1 4/84

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1985

CONSERVATION DIVISION
Wichita, Kansas