

To: 1 020516 9-17
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION E/2 W/2 SW, SEC. 31, T. 33 S, R. 43 W/4
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,446 0001 278
1320 feet from S section line
4030 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447
Operator: OXY USA INC.
Name & Address: P.O. Box 26100
Oklahoma City, OK 73126-0100

Lease Name Jackson A Well # 1
County Morton 152.75
Well Total Depth 4700 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1420

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address Liberal, KS

Company to plug at: Hour: 10:15 a.m. Day: 15 Month: 9 Year: 19 92

Plugging proposal received from Doug Blair
(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 4647', TOC 3170', PBTD 4575', Perfs at 4491-95'
1st plug set CIBP at 4480' with 2 sx cement on top with bailer,

2nd plug load hole with heavy mud and pump 100 sx cement at 2600',

3rd plug pump 50 sx cement at 1420',

4th plug pump 30 sx cement at 700', 5th plug pump 10 sx cement at 40 to -4'

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 10 a.m. Day: 17 Month: 9 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4480' with 2 sx cement on top with bailer,

2nd plug loaded hole with heavy mud and pumped 100 sx cement at 2600',

3rd plug pumped 50 sx cement at 1420',

4th plug pumped 30 sx cement at 700',

5th plug pumped 10 sx cement at 40 to -4'.
Heavy mud between all plugs.

Remarks: Used common cement by Sargent's. Recovered 2823' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 10-21-92

INV. NO. 36537

Signed Glenn R. Barlow (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1992
CONSERVATION DIVISION
WICHITA, KANSAS
Glenn R. Barlow
(TECHNICIAN)