

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10354-00-00
Spot: CSW Sec/Twnshp/Rge: 35-33S-43W
3960 feet from N Section Line, 1320 feet from W Section Line
Lease/Unit Name: COUNCIL Well Number: 1-35
County: MORTON Total Vertical Depth: 3194 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN, LLC
Address: 3200 FIRST PLACE TOWER
TULSA, OK 74103

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 624 WITH 400 SX CMT
Production: Size 5.5 feet: 3192 WITH 375 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/18/2000 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: SET CIBP @ 2782' WITH 2 SX CMT. SPOT 50 SX CMT AT 1600'. SPOT 50 SX CMT AT 650'. SET 10 SX CMT AT 0-40'.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/19/2000 11:30 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 2861-3029'. SET CIBP @ 2782' WITH 2 SX CMT ON TOP WITH DUMP BAILER. SHOT CASING AT 800'. CASING WAS NOT FREE. SHOT CASING AT 665'. PULLED TO 660'. TRIED TO LOAD HOLE WITH 60 BBLs MUD. PUMPED 50 SX CMT WITH 100# HULLS. DISPLACED WITH MUD. HOLE DIDN'T CIRCULATE. PULLED CASING OUT OF HOLE. ON 12/19/00 TAGGED CMT AT 487'. LOADED HOLE WITH 10 SX CMT.

RECEIVED
STATE CORPORATION COMMISSION
DEC 20 2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 665' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Kevin D Strube
(TECHNICIAN)

INVOICED
DATE 12/22/00
INV. NO. 2001061

DEC 19 2000

AD