

1 060642

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,066 - 0000

SE NW NE, SEC. 2, T 34 S, R 11 W
4290 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9869

Lease Name Ott-O'Neil Well # 1-2

Operator: Chapman Energy Oklahoma, Inc.
Name & Address 120 S. Market, Suite 320
Wichita, KS 67202

County Barber 152.75
Well Total Depth 4700 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 439

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 East Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 2:00 am Day: 15 Month: August Year: 19 85

Plugging proposal received from Judy Steiben

(company name) White & Ellis - Great Bend (phone) 316-792-2424

where: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 345'
Elevation 1423'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 430' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN) X

Plugging Operations attended by Agent?: All _____ Part _____ None _____

Operations Completed: Hour: 4:30 am Day: 15 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1380' with 50 sx cement, 2nd plug at 430' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.) R.W.L.

INVOICED (date) (if not) observe this plugging. RECEIVED

DATE 8-20-85

INV. NO. 9684

Signed Paul A. Luthi
(TECHNICIAN)

AUG 20 1985