

1 040456

8-27

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,616-0000

N/2 NE SW, SEC. 12, T 35 S, R 13 W/E
2310 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Lease Name Meyer Well # 2

Operator: Okmar Oil Company

County Barber 157.07

Name & Address: Box 723

Well Total Depth 4833 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 358

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1 p.m. Day: 27 Month: 8 Year: 19 90

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4819' w/150 sx cement, Perfs at 4816-26'

1st plug sand back to 4765' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 27 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4765' and dumped 4 sx cement on top of
sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10
sx gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 450 psi and shut in 250 psi.

AUG 29 1990

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3750' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
I (David H. Kunkle) observe this plugging.

Signed Stephen J. Puffer
(TECHNICIAN)

DATE: 8-30-90

INV. NO. 29180