

1. 040455

8-27

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-20,334-0000

C NW SE, SEC. 12, T 35 S, R 13 W X E
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Lease Name Meyer B Well # 1

Operator: Okmar Oil Company

County Barber 158.66

Name & Address Box 723

Well Total Depth 4882 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 27 Month: 8 Year: 19 90

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4881' w/100 sx cement, Perfs at 4862-72, 4840-44'

1st plug sand back to 4790' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 27 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4790' and dumped 4 sx cement on top of
sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1250' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
I hereby authorize you to observe this plugging.

DATE: 8-30-90

Signed Stephen J. Pfeiffer (TECHNICIAN)

INV. NO. 29181