

To: 1 020656  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,741-0001  
NE NE SW, SEC. 11, T 32 S, R 34 W/R

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417  
Operator: Union Pacific Resources Company  
Name & Address P.O. Box 7, MS 3407  
Ft. Worth, TX 76101-0007

2300 feet from S section line  
3180 feet from E section line

Lease Name E. Paul Boles Well # 2-11  
County Seward 185.25

Well Total Depth 5700 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1659

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor J.W. Gibson License Number 5866

Address P.O. Box 160, Ft. Morgan, CO 80701

Company to plug at: Hour: 10 a.m. Day: 7 Month: 4 Year: 19 93

Plugging proposal received from Tim Hintergardt

(company name) J.W. Gibson (phone) 303-867-3058

were: 5 1/2" at 5686' w/800 sx cement, EBTD 4455', Perfs at 4808-24, 4176-85'

1st plug set CIBP at 4775' with 2 sx cement on top,

2nd plug set CIBP at 4125' with 2 sx cement on top, load hole with mud with tubing,

3rd plug pump 25 sx cement at 1671', 4th plug pump 25 sx cement at 660',

5th plug pump 5 sx cement at 35-0'.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:45 p.m. Day: 8 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4775' with 2 sx cement on top,

2nd plug set CIBP at 4125' with 2 sx cement on top, loaded hole with mud with tubing,

3rd plug pumped 25 sx cement at 1671',

4th plug pumped 25 sx cement at 660',

5th plug pumped 5 sx cement at 35-0'.

RECEIVED  
STATE CORPORATION COMMISSION

APR 14 1993

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Gibson. No casing recovery.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE 4-23-93

Signed Glenn R. Barlow  
(TECHNICIAN)

INV. NO. 37606  
4-8