

To: 1 020676
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-25

API NUMBER 15- 175-20,797-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Operator: Union Pacific Resources Company
Name:

Address P.O. Box 7 - MS 3407

Ft. Worth, TX 76101-0007

C NE NW, SEC. 11, T. 32 S, R. 34 W/E

4620 feet from S section line

3300 feet from E section line

Lease Name Fitzgerald C. Well # 4-11

County Seward 183.62

Well Total Depth 5650 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1676

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor J.W. Gibson License Number 5866

Address P.O. Box 160, Ft. Morgan, CO 80701

Company to plug at: Hour: 11 a.m. Day: 24 Month: 5 Year: 19 93

Plugging proposal received from Tim Hintergardt

(company name) J.W. Gibson (phone) 303-867-3058

were: 5 1/2" at 5649' w/875 sx cement, PBTD 4750', Perfs at 4211-21'

CIBPs at 5500', 4830', and 4750'

1st plug set CIBP at 4150' with 2 sx cement on top, load hole with mud,

2nd plug pump 40. sx cement at 1650' with tubing,

3rd plug pump 30 sx cement at 700', 4th plug pump 5 sx cement at 40', 5th plug fill 8 5/8"

to surface.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:15 p.m. Day: 25 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4150' with 2 sx cement on top, loaded hole w/mud

2nd plug pumped 40' sx cement at 1650' with tubing,

3rd plug pumped 30 sx cement at 700',

4th plug pumped 5 sx cement at 40',

5th plug filled 8 5/8" to surface with 10 sx cement.

Remarks: Used common cement by Gibson. No casing recovery.

(If additional description is necessary, use BACK of this form)

(If applicable) observe this plugging.

DATE 6-8-93

INV. NO. 37858

Signed Glenn R Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

JUN 4, 1993

CONSERVATION DIVISION
Wichita, Kansas