

1 020235

5-19

95

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 110'
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,667-0000

W NW NW, SEC. 12, T 32 S, R 34

4620 feet from S section line

4730 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Hoffman E Well # 3

Operator: OXY USA Inc.

County Seward 183.63

Name & Address P.O. Box 26100

Well Total Depth 5650 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1646

Abandoned Oil Well Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Company License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 1 p.m. Day: 11 Month: 5 Year: 19 89

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Company (phone) 316-624-7455

were: 5 1/2" at 5648' PBTD 4635' Perfs at 4159-69' DV tool at 4903' w/225 sx cement
TOC 3290'

1st plug set CIBP at 4100' with 2 sx cement on top,

2nd plug at Chase with 100 sx if deep enough or 25 sx on stub,

3rd plug at 1646' with 50 sx cement, 4th plug at 800' with 30 sx, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1 p.m. Day: 19 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4100' with 2 sx cement on top,

2nd plug load hole with heavy mud, pump 35 sx cement at 2500',

3rd plug ran 50 sx cement at 1700-1600',

4th plug pumped 30 sx cement at 800',

5th plug pumped 10 sx cement at 40-0'.

RECEIVED STATE CORPORATION COMMISSION JUN 20 1989 CONSERVATION DIVISION Wichita, Kansas

6-26-89

Remarks: Used common cement by Sargent's. Recovered 2533' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 6-27-89

Signed [Signature] (TECHNICIAN)

INV. NO. 25131