

1700343

TO: STATE CORPORATION COMMISSION

API NUMBER 15-175-20,698-0000  
C S/2 NW SW SEC. 12, T 32 S, R 34 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HOFFMAN R WELL # 1

TECHNICIAN'S PLUGGING REPORT

3/28

COUNTY SEWARD 188.44

OPERATOR LICENSE # 5447

WELL TOTAL DEPTH 5798 FEET

OPERATOR: OXY USA INC

PRODUCTION CSG: SIZE 5 1/2" @ 5797' WITH 200 SX

NAME AND BOX 2528

SURFACE CASING: SIZE 8 5/8" @ 1635' WITH 775 SX

ADDRESS LIBERAL, KS 67950-2528

RECEIVED  
STATE CORPORATION COMMISSION

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

APR 10 2000

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC.

CONSERVATION DIVISION  
LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 12:00 PM DAY: 28 MONTH: 03 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC. (PHONE) 580-854-6515

WERE: PERFS AT 5357-5366

1ST PLUG SPOT 200# HULLS WITH 25 SX CEMENT TO 5357'-5157'. SQUEEZED PERFS AT 1200 PSI.

CIRCULATE HOLE WITH MUD. 2ND PLUG SHOOT CASING AT 1703' AND SPOT 65 SX CEMENT FROM 1660'

TO 1460'. GOOD CIRCULATION. 3RD PLUG SPOT 50 SX CEMENT AT 550' TO 400'. 4TH PLUG SPOT

10 SX CEMENT FROM 40' TO 0'.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 28 MONTH: 03 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG SPOT 200# HULLS WITH 25 SX CEMENT TO 5357'-5157'. SQUEEZED PERFS AT 1200 PSI.

CIRCULATE HOLE WITH MUD. 2ND PLUG SHOOT CASING AT 1703' AND SPOT 65 SX CEMENT FROM 1660'

TO 1460'. GOOD CIRCULATION. 3RD PLUG SPOT 50 SX CEMENT AT 550' TO 400'. 4TH PLUG SPOT

10 SX CEMENT FROM 40' TO 0'.

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 1703' WITH 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED SIGNED Gary Winters  
(TECHNICIAN)

DATE 4/12/00

FORM CP-2/3

INV. NO. 061533