

1 020377

4-29

413

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19- 175-21,143-0000

SE NW SE, SEC. 14, T. 32 S, R. 34 W

1800 feet from S section line

1700 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Stoner A Well # 3

Operator: OXY USA Inc.

County Seward 209.62

Name & Address P.O. Box 26100

Well Total Depth 6450 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1705

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor OXY USA Inc. License Number 5447

Address P.O. Box 26100, Oklahoma City, OK 73126-0100

Company to plug at: Hour: 9 a.m. Day: 29 Month: 4 Year: 19 91

Plugging proposal received from Bill Smith

(company name) OXY USA Inc. (phone) 316-675-2293

were: 5 1/2" at 3019' cemented to surface, PBTD 2974', Perfs at 2588-2694',

1st plug set CIBP at 2550' with 2 sx cement on top,

2nd plug spot 30 sx cement at 1805-1605',

3rd plug pump 50 sx cement at 800-400',

4th plug pump 10 sx cement at 65-0'.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 p.m. Day: 29 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2500' with 2 sx cement on top,

2nd plug ran tubing, circulated heavy mud and spotted 30 sx cement at 1805-1605',

3rd plug pumped 50 sx cement at 800-400',

4th plug pumped 10 sx cement at 65-0'.

Remarks: Used Class H cement by Halliburton. No casing recovery.

(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

Signed Glenn R. Barber (TECHNICIAN)

DATE 5-13-91

MAY 06 1991

INV. NO. 31793

CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3 Rev. 01-84