

1100347

TO: STATE CORPORATION COMMISSION

API NUMBER 15-175-21,296 - 0000
C N/2 SW/4 SEC. 16, T 32 S, R 34 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3960 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME KAPP A WELL # 4

TECHNICIAN'S PLUGGING REPORT

COUNTY SEWARD 207.16

OPERATOR LICENSE # 5447

WELL TOTAL DEPTH 6374 FEET

OPERATOR: OXY USA INC

PRODUCTION CSG: SIZE 5 1/2" @ 6374' WITH 1230 SX

NAME AND BOX 2528

SURFACE CASING: SIZE 8 5/8" @ 1688' WITH 630 SX

ADDRESS LIBERAL, KS 67950-2528

RECEIVED
STATE CORPORATION COMMISSION

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL APR 17 2000

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. LICENSE NUMBER

CONSERVATION DIVISION
Wichita, Kansas

ADDRESS RT. 1, BOX 49BA TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 11 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC. (PHONE) 580-854-6515

WERE: PERFS AT 6120-6180

1ST PLUG SPOT 25 SX CEMENT WITH 200# HULLS. PRESSURE WENT FROM 200 PSI TO 1200 PSI.

2ND PLUG CIRCULATE HOLE, SPOT 50 SX CEMENT PLUG AT 900'. 3RD PLUG CIRCULATE HOLE, SPOT

50 SX CEMENT PLUG AT 450'. 4TH PLUG FILL WITH MUD. MIX 10 SX CEMENT FROM 40' TO 0'.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:00 PM DAY: 11 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG SPOT 25 SX CEMENT WITH 200# HULLS. PRESSURE WENT FROM 200 PSI TO 1200 PSI.

2ND PLUG CIRCULATE HOLE. SPOT 50 SX CEMENT PLUG AT 900'. 3RD PLUG CIRCULATE HOLE. SPOT

50 SX CEMENT PLUG AT 450'. 4TH PLUG FILL WITH MUD. MIX 10 SX CEMENT FROM 40' TO 0'.

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 914' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED
DATE 4/20/00
WELL NO. 066620

SIGNED Gary Winters
(TECHNICIAN)

FORM CP-2/3