

020237

6-30

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,776-0001
NE NE SW, SEC. 20, T 32 S, R 34 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

2310 feet from S section line
2970 feet from E section line

Operator: OXY USA Inc.
Name &
Address P.O. Box 26100
Oklahoma City, OK 73126-0100

Lease Name Hitch 0 Well # 1
County Seward 208.00
Well Total Depth 6400 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1699

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 9 a.m. Day: 29 Month: 6 Year: 19 89

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 6399' PBD 3092' Perfs at 2968-3014' TOC on 5 1/2" was 2040'

1st plug set CIBP at 2910' with 2 sx cement,

2nd plug loaded hole with mud and shot pipe off at 1760', pump : 50 sx cement at 1730'

3rd plug pump 40 sx cement at 850',

4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 10:30 a.m. Day: 30 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2910' with 3 sx cement on top,

2nd plug loaded hole with mud and shot pipe off at 1760', pumped 50 sx cement at 1730',

3rd plug pumped 40 sx cement at 850',

4th plug pumped 10 sx cement at 40' to -3'.

RECEIVED
STATE CORPORATION COMMISSION
JUL - 5 1989

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 1760' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(If you observe this plugging.)

INVOICED

Signed Glenn R. Barlow (TECHNICIAN)

DATE 7-6-89

INV. NO. 25219 6-30