

1 060644

API NUMBER 15- 175-20,840 ~ 0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE SW, SEC. 23, T 32 S, R 34 W ⁽¹⁾ EX

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Baughman Well # X-1

Operator: Cities Service Oil & Gas Corp.
Name & Address 3545 N.W. 58th Street
Oklahoma City, OK 73112

County Seward 209.63

Well Total Depth 6450 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1705

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Daco, Inc. License Number 6416

Address Drawer 3010, Borger, TX 79007

Company to plug at: Hour: 6:00 pm Day: 20 Month: August Year: 19 85

Plugging proposal received from Charles Glasscock

(company name) Cities Service (phone) 405-949-4400

were: 5 1/2" at 6499' PBD 6395' Perfs at 5703-5706' mud between plugs
Spot cement through 5 1/2" casing with

1st plug set CIBP at 5660' with 2 sx cement

2nd plug shoot off point with 50 sx cement

3rd plug at 1735' with 50 sx cement

4th plug at 650' with 35 sx cement
solid bridge

5th plug hulls - plug at 40' - Plugging Proposal Received by Paul A. Luthi
cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 7:00 pm Day: 20 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5660' with 2 sx cement, 2nd plug at 2410' with 50 sx cement, 3rd plug at 1735' with 50 sx cement, 4th plug at 650' with 35 sx cement,

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Recovered 2420' .5 1/2" casing. Used common cement by Daco.
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Paul A. Luthi
(TECHNICIAN)

DATE AUG 28 1985

INV. NO. 9810 8-20 SEP 24 1985
CONSERVATION DIVISION