

1 051946 8-14

API NUMBER 15- 175-20,777-0001

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

SE SE SE, SEC. 26, T 32 S, R 34 W/EX
330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Hitch N Well # 1

Operator: OXY USA INC.

County Seward

Name: P.O. Box 26100

Well Total Depth 6430 208.98 feet

Address Oklahoma City, OK 73126-0100

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1686

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor J.W. Gibson License Number 5866

Address 518 17th St., Ste. 1250, Denver, CO 80640

Company to plug at: Hour: 8 a.m. Day: 14 Month: 8 Year: 19 95

Plugging proposal received from James Mongold

(company name) OXY USA INC. (phone) 316-675-2293

logs: 5 1/2" at 5929' w/350 sx cement, PBTD 5842', Perfs at 5713-19, 5706-19'

1st plug set CIBP at 5650' and dump 2 sx cement on top,

2nd plug at 1716' with 50 sx cement,

3rd plug at 640' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 8:30 p.m. Day: 14 Month: 8 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5650' and dumped 2 sx cement on top,

2nd plug at 1716' with 50 sx cement,

3rd plug at 640' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Filled hole with 9# mud.

RECEIVED STATE CORPORATION COMMISSION

AUG 16 1995

Remarks: Used common cement by J.W. Gibson. Recovered 1730' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

Signed Richard W. Lacy (TECHNICIAN)

DATE 8-28-95

NOV 02 1995 8-14