

1 020331

9-24

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-21,003-0001

SE SE NE, SEC. 26, T 32 S, R 34 W/X

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Boyer B Well # 2

Operator: OXY USA Inc.

County Seward 209.62

Name & Address P.O. Box 26100

Well Total Depth 6450 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size 20" feet 40

Surface Casing: Size 8 5/8 feet 1667

Abandoned Oil Well Gas Well X Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor OXY USA Inc. License Number 5447

Address P.O. Box 26100, Oklahoma City, OK 73126-0100

Company to plug at: Hour: 4 p.m. Day: 21 Month: 9 Year: 19 90

Plugging proposal received from Bill Smith

(company name) OXY USA Inc. (phone) 316-675-2293

were: 5 1/2" at 3125'w/650 sx cement, PBDT 2690', Perfs at 2585-95, 2613-20, 2623-27,
2644-80, 2694-2726' CIBP at 2690'

1st plug set CIBP at 2500' with 2 sx cement on top,

load hole with mud and spot through tubing:

2nd plug at 1770' with 30 sx cement, 3rd plug at 800' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1 p.m. Day: 24 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2500' with 2 sx cement on top (9/21/90),
Ran tubing to bottom at 2480' and circulated hole with jet mud,
2nd plug pumped 30 sx cement at 1780-1540',

3rd plug pumped 50 sx cement at 800-420',

4th plug pumped 10 sx cement at 60-0'.

RECEIVED
STATE CORPORATION COMMISSION

OCT 4 1990

Remarks: Used Class H cement by Halliburton. No casing recovery. 5 1/2" cemented to 0'.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-10-90

INV. NO. 29618

observe this plugging.

Signed [Signature]
(TECHNICIAN)