

To: 1 100121
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15- Completed in 4/57
C NE SW, SEC. 27, T 32 S, R 34 W/4
1980 feet from S section line
3300 feet from E section line

Operator License # 5447
Operator: OXY USA Inc.
Name & Address: P.O. Box 300
Tulsa, OK 74102

Lease Name Hitch F Well # 2
County Seward 208.00
Well Total Depth 6400 feet
Conductor Pipe: Size 13 3/8 feet 598
Surface Casing: Size 8 5/8 feet 2325

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Gibson Well Service License Number 5866
Address 7400 E. Orchard Rd., Ste. 370, Englewood, CO 80111-2531

Company to plug at: Hour: 9 a.m. Day: 30 Month: 4 Year: 19 97

Plugging proposal received from Reid Wilson
(company name) Halliburton (phone) 316-629-3578

Work: 5 1/2" at 4550' w/700 sx cement, PBTD 4145', Perfs at 4181-4211'
1st plug set CIBP at 4160' with 2 sx cement on top, 2nd plug perforate at 3005-3010' and
pump 100 sx cement with hulls,
3rd plug at 2345' with 100 sx cement, 4th plug at 594' with 90 sx cement,
5th plug pump 10 sx cement from 40-0'.

RECEIVED
KANSAS CORP COMM
MAY - 8
1:0

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 1 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4160' and dumped 2 sx cement on top with bailer,
2nd plug perforated at 3005-3010' and pumped 100 sx cement with hulls. Squeezed off gas zone,
ran free point, 3rd plug spotted 100 sx cement at 2345', displaced with gel,
4th plug spotted 90 sx cement at 594', displaced with gel,
5th plug topped off with 10 sx cement from 40-0'.

Remarks: Used Halliburton Lite 3% cc cement by Halliburton. Recovered 2350' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE MAY 13 1997
INV. NO. 48093
5-1

Signed Gary Winters (TECHNICIAN)