

1100346

TO: STATE CORPORATION COMMISSION

API NUMBER 15-175-20,854-0000
SE SE NW SEC. 28, T 32 S, R 34 W

CONSERVATION DIVISION - PLUGGING SECTION 2970 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2875 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HITCH R WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY SEWARD 209.63

OPERATOR LICENSE # 5447

WELL TOTAL DEPTH 6450 FEET

OPERATOR: OXY USA, INC. PRODUCTION CSG: SIZE 5 1/2" @ 6449' WITH 175 SX

NAME AND PO BOX 2528 SURFACE CASING: SIZE 8 5/8" @ 1697' WITH 800 SX

ADDRESS LIBERAL, KS 67905

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 07 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC (PHONE) 580-854-6515

WERE: PERFS AT 6132-6142

ON 04/06/00 1ST PLUG PUMP 200# HULLS & 25 SX CEMENT FROM 6132-5932. 2ND PLUG AT 1703'

WITH 50 SX CEMENT. GOOD CIRCULATION. 3RD PLUG AT 600' WITH 50 SX CEMENT. GOOD

CIRCULATION. 4TH PLUG AT 40-0' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 4:30 PM DAY: 07 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT _____

ON 4/6/00 1ST PLUG PUMP 200# HULLS & 25 SX CEMENT FROM 6132-5932. ON 4/7/00 2ND PLUG AT

1703' WITH 50 SX CEMENT. GOOD CIRCULATION. 3RD PLUG AT 600' WITH 50 SX CEMENT. GOOD

CIRCULATION. 4TH PLUG AT 40-0' WITH 10 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

APR 17 2000

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 1714' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

DATE 4/20/00

SIGNED Gary Winters
(TECHNICIAN)

FORM CP-2/3

W.M. B.S.L. 04/20/00

(R)