

To: 1 100125 5-7
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-175-21,167-0000
140' W of N/2 N/2, SEC. 29, T. 32 S, R. 34 W/X

TECHNICIAN'S PLUGGING REPORT
Operator License # 5447
Operator: OXY USA Inc.
Name & Address: P.O. Box 300
Tulsa, OK 74102



4620 feet from S section line
2780 feet from E section line
Lease Name Hitch B Well # 2
County Seward 209.63
Well Total Depth 6450 feet
Conductor Pipe: Size 20 feet 40
Surface Casing: Size 8 5/8 feet 1720

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor J.W. Gibson Well Service Co. License Number 5866
Address 7400 E. Orchard Rd., Ste. 370, Englewood, CO 80111-2531

Company to plug at: Hour: 11 a.m. Day: 7 Month: 5 Year: 19 97

Plugging proposal received from Reid Wilson
(company name) Halliburton (phone) 316-629-3578

Perfs: 5 1/2" at 6450' w/630 sx cement, DV @ 3276' w/590 sx cement, CIBP 6100' w/1 sx cmt. in 1996
Perfs at 6136-46, 6150-64, 5783-92'

1st plug pump 2 sx hulls and 50 sx cement above perfs.
2nd plug cement from 3200-2400';
3rd plug cement from 1800-1500', 4th plug at 700' with cement and gel.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 7 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pump 50 sx cement with 3 sx hulls at 5816',
2nd plug spot 100 sx cement at 3210', gel spacer,
3rd plug spot 50 sx cement at 1758', gel spacer,
4th plug spot 70 sx cement at 714' to surface.
Checked 8 5/8" annulus with 1 bbl. to surface.

RECEIVED
KANSAS CORP COMM
MAY 13 10 12 59

Remarks: Used Halliburton Lite 2% cc by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
(I should observe this plugging.)

DATE MAY 14 1997

Signed Gary Winters (TECHNICIAN)

INV. NO. 48114
5-7