

To: 1020830 12-16
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,587-0000
SW NW NW, SEC. 31, T 32 S, R 34 W/E
4280 feet from S section line
4980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447
Operator: OXY USA Inc.
Name:
Address P.O. Box 26100
Oklahoma City, OK 73126-0100

Lease Name Hitch Well # J-2
County Seward 20670
Well Total Depth 6360 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1715

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated
Plugging Contractor OXY USA Inc. License Number 5447
Address P.O. Box 26100, Oklahoma City, OK 73126-0100

Company to plug at: Hour: 1 p.m. Day: 15 Month: 12 Year: 19 94
Plugging proposal received from J. Piland
(company name) OXY USA, Inc. (phone) 316-629-4200

were: 5 1/2" at 6360', TOC 5800', Perfs at 6100-6119', CIBP at 6070'
1st plug perforate at 3000', run cement retainer and pump 100 sx cement,
2nd plug run tubing to 1830' and pump 60 sx cement,
3rd plug pump 50 sx cement at 650',
4th plug circulate cement at 40-0' with 10 sx.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 11 a.m. Day: 16 Month: 12 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug perforated at 3000' and ran cement retainer, pumped 100 sx cement,
2nd plug ran tubing to 1830' and pumped 60 sx cement,
3rd plug pumped 50 sx cement at 650',
4th plug circulated cement at 40-0' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 2% cc by D & S. Recovered 1822' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 1-4-95
INV. NO. 41957

Signed Glenn R. Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1994