

YD
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Cities Service Oil Co.

Complete Address: Box 1028 Guymon, Okla.

Lease Name Sharpe Well No. C-1

Location SW SW NE Sec. 20 Twp. 33 Rge. 43 (E) (W)

County Morton Total Depth 3438'

Abandoned Oil Well Gas Well x Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Daco Well Service

Address: Borger, Texas License No. 138

Operation Completed: Hour 4 PM Day 25 Month 7 Year 63

The Above well was plugged as follows:

8 5/8" 360' Circulated w/cement. 5 1/2" 3436' Cemented. Perforations 3056' to 2960'

Plug bottom w/15 sax.cement, top cement 2805' Mud 2805' to 450'

30 Sax.cement spotted at 450' to 350' Mud 350' to 30'

10 Sax.cement, Plug, 30' to surface.

Pulled 810' 5 1/2" Pipe. Company Pump. Weld cap on surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Hugh D. ...*
Well Plugging Supervisor

DATE 8/9/63

INV. NO. 7552-U