

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company

Complete Address Box 1228, Guymon, Oklahoma 73942

Lease Name Fletcher "C" Well No. 1

Location NWNW SE Sec. 27 Twp. 33 Rge. 43 (EX) (W)

County Morton Total Depth 3425'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Daco Lease & Well Service

Address Borger, Texas License No. 138

Operation Completed: Hour 2:00PM Day 16 Month 12 Year 1969

The above well was plugged as follows:

8 5/8" to 600' circulated w/ cement. 5 1/2" to 3424' cemented.

Top perforations 2926' Plug bottom w/ 20 sacks cement.

Top of cement 2727' Mud 2727' to 600'

Spotted 40 sacks cement 600' to 440' Mud 440' to 30'

Plug. Halls & 10 sacks cement 30' to 0'. Company Pump

Pulled 1096' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edward J. Evers
Well Plugging Supervisor

DATE 12/19/69
INV. NO. 1082-24