

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 24 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Colorado Oil & Gas Corporation

Complete Address: P. O. Box 158, Liberal, Kansas

Lease Name Campbell Well No. # 1-33

Location SW SW NE Sec. 33 Twp. 33 Rge. 43 (E) (W) W

County Morton Total Depth 3153'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Sargent Casing Pulling Service

Address: 121 West 9th St., Liberal, Kansas License No. 511

Operation Completed: Hour 2:00 PM Day 20th Month August Year 1965

The Above well was plugged as follows:

612' of 8 5/8" surface pipe, cement circulated. 3153' of 5 1/2" long string,
cemented with 350 sacks. Temperature survey 1600'. Top perferation 2851'.
Bottom of the hole was cemented with 20 sacks at 2700'. 1025' of 5 1/2" long
string was recovered from the hole. At 600' 35 sacks of cement was pumped.
At 40' hole was cemented with 10 sadks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 8-24-65

INV. NO. 1676-W